



RF cables from antennas to pre-selector should be as short as possible.
 Pre-selector should be mounted near the antennas.
 Pre-selector control cable is custom made to length.
 All cables will have lightning protectors installed and properly grounded to single point ground bar.
 All AC power will be via a UPS.